



CONTACT INFORMATION

Mining Records Curator
Arizona Geological Survey
1520 West Adams St.
Phoenix, AZ 85007
602-771-1601
<http://www.azgs.az.gov>
inquiries@azgs.az.gov

The following file is part of the

Arizona Department of Mines and Mineral Resources Mining Collection

ACCESS STATEMENT

These digitized collections are accessible for purposes of education and research. We have indicated what we know about copyright and rights of privacy, publicity, or trademark. Due to the nature of archival collections, we are not always able to identify this information. We are eager to hear from any rights owners, so that we may obtain accurate information. Upon request, we will remove material from public view while we address a rights issue.

CONSTRAINTS STATEMENT

The Arizona Geological Survey does not claim to control all rights for all materials in its collection. These rights include, but are not limited to: copyright, privacy rights, and cultural protection rights. The User hereby assumes all responsibility for obtaining any rights to use the material in excess of "fair use."

The Survey makes no intellectual property claims to the products created by individual authors in the manuscript collections, except when the author deeded those rights to the Survey or when those authors were employed by the State of Arizona and created intellectual products as a function of their official duties. The Survey does maintain property rights to the physical and digital representations of the works.

QUALITY STATEMENT

The Arizona Geological Survey is not responsible for the accuracy of the records, information, or opinions that may be contained in the files. The Survey collects, catalogs, and archives data on mineral properties regardless of its views of the veracity or accuracy of those data.

PRINTED: 08/28/2001

ARIZONA DEPARTMENT OF MINES AND MINERAL RESOURCES AZMILS DATA

PRIMARY NAME: HIDDEN TREASURE

ALTERNATE NAMES:

YAVAPAI COUNTY MILS NUMBER: 1233A

LOCATION: TOWNSHIP 10 N RANGE 2 E SECTION 7 QUARTER SE
LATITUDE: N 34DEG 15MIN 16SEC LONGITUDE: W 112DEG 10MIN 40SEC
TOPO MAP NAME: CLEATOR - 7.5 MIN

CURRENT STATUS: DEVEL DEPOSIT


COMMODITY:

GOLD
LEAD
ZINC

BIBLIOGRAPHY:

ADMMR HIDDEN TRESURE MINE FILE
USGS CLEATOR QUAD
ARIZONA MINING JOURNAL JAN. 1918 P 24
CLAIMS EXTEND INTO SEC. 8
USGS BULL 782, P 158
USGS IC 6905
USGS BULL 1345, P. 34

R 2 E



T 11 N

T 10 N

LOCATION OF HIDDEN TREASURE MINE

Scale 1 : 62500

RECONSTRUCTION FINANCE CORPORATION

WASHINGTON

325 Heard Building
Phoenix, Arizona
March 3, 1943

3-3754

*Recd
3-3-43*

Mr. Earl Hastings
State Dept. of Mineral Resources
413 Home Builders Building
Phoenix, Arizona

Re: Hidden Treasure Mining Co.
Docket No. Phoenix C-143 ✓

Dear Earl:

Enclosed find Hidden Treasure Application, Docket No. C-143, on which we would like your analysis and report. You will note that upon receipt of this application on February 20 we wrote the applicant for more satisfactory data and an explanation of his assays. He replies under date of March 1.

If one accepts the data here at its face value it makes quite a showing. The data and opinions are all furnished by R. W. Bondurant, John Slak and A. C. Haigler. What do you think of it? One thing we should have asked him and didn't is just exactly what their program is, and you might determine that for us. They talk about pumping out a winze, but nowhere can I find out just where they are going to sink if they are going to sink.

Yours very truly,

W. B. Gohring
W. B. GOHRING
Supervising Engineer

WBG:ml

Enclosure

Application and accompanying data



at Cortez by Hadden ~~Smith~~ m

Order +

Johnnie B. Hayes

Rt 12 Box 1126

Phon

GENERAL COMMENTS GEN <

* GENERAL REFERENCES

REFERENCE 1 F1 < AR DEPT MIN. RE - ES FILE DATA

REFERENCE 2 F2 < ABGMT BULL 140, p. 102

REFERENCE 3 F3 < USGS BULL 702, p. 15B

REFERENCE 4 F4 < USGS BULL 1345, p. 34

U.S. CRIB-SITE FORM

RECORD IDENTIFICATION

RECORD NUMBER B10 < >
REPORT DATE G1 < 81 Y. 09 >
YR. MO.

RECORD TYPE B20 < X, 1, M >
INFORMATION SOURCE B30 < 1, 2 >

DEPOSIT NUMBER B40 < >
FILE LINK IDENT. B50 < USGM 004 025 1130 >

REPORTER(SUPERVISOR) G2 < DEWITT, ED, H >
(last, first, middle initial)

REPORTER AFFILIATION G5 < ABGMT > SITE NAME A10 < HIDDEN TREASURE MINE >
SYNONYMS A11 < >

LOCATION

MINING DISTRICT/AREA A30 < RICHINGAIL DISTRICT >
COUNTY A60 < YAVAPAI >

STATE A80 < AZ > COUNTRY A40 < U.S. >

PHYSIOGRAPHIC PROV A63 < 1, 2, 3 >
DRAINAGE AREA A62 < 1, 5, 0, 7, 0, 1, 0, 2, 3 >

LAND STATUS A64 < 0, 0, 1, 1, 1, 1 >

QUADRANGLE NAME A90 < CLEATOR (1974) >

QUADRANGLE SCALE A100 < 24,000 >

SECOND QUAD NAME A92 < >

SECOND QUAD SCALE A91 < >

ELEVATION A107 < 3,075 M.F.T. >

UTM

NORTHING A120 < 37,907,000 >
EASTING A130 < 39,145,000 >
ZONE NUMBER A110 < 18 >

*ACCURACY

ACCURATE ACC (circle)
ESTIMATED EST < >

GEODETIC

*LATITUDE A70 < 34-15-13 N >
*LONGITUDE A80 < 112-10-44 W >

CADASTRAL

TOWNSHIP(S) A77 < 010N >
SECTION(S) A79 < 7 >
SECTION FRACTION(S) A76 < SE OF SE SW OF SW >
MERIDIAN(S) A81 < GILA AND SALT RIVER >

*RANGE(S) A78 < 010E >

POSITION FROM NEAREST PROMINENT LOCALITY A82 < 4.3 MILES SOUTHEAST OF CLEATOR, ARIZONA >

LOCATION COMMENTS A83 < >

ESSENTIAL INFORMATION
ESSENTIAL SOMETIMES OR HIGHLY RECOMMENDED

NAME OF MINE: HIDDEN TREASURE

COUNTY: YAVAPAI C.
DISTRICT: BLACK CANYON
METALS: PB, ZN, CU, AG

OPERATOR AND ADDRESS:

MINE STATUS

DATE:

DATE:

Hidden Treasure Mng. Co. Inc.
137 W. Monroe Street, Phoenix 1/44

RFC loan granted
Shut down

5/45

Irwin Otis + Whittacre,
Bumblebee

5/45
1/47

Reconditioning Mill
Idle

HIDDEN TREASURE

Cu, Pb, Zn

Yavapai

13 - 6

T 10 N, R 1 E

Irvin Otis, Bumblebee unclaimed 6-13-46

'45

CRAINE, O. H.
RT. 12 Box 1136
Phoenix, Arizona

'48

HIDDEN TREASURE, Yavapai Co.

SHATTUCK DENN MINING CORPORATION
and
SUBSIDIARIES

Humboldt Office

Date May 9, 1966

TO: C.R. Sundeen

FROM: J. Olaf Sund

SUBJECT: HIDDEN TREASURE MINE
% Mr. Eldred Lane, Vice President
Pope & Talbott, Inc.
San Francisco, Calif.
Agent: Mr. Guy Mitchell-Bumblebee
Phone 2

INTRODUCTION:

At Jack Pierce's request, the Hidden Treasure property near Cleator was re-examined.

TYPE: Gold?

TERMS REQUESTED: Not Known.

LOCATION:

The property includes ten unpatented claims as follows: Curley Lode, Gold Reef and White Tip, all recorded in book 95, pages 580 to 582; Golden Reef No. 1, Golden Reef No. 2 recorded in book 107, pages 175 and 176; Kitty in book 113, page 517; Treasure Mount, in book 117, page 180; Treasure Mount No. 2 in book 119, page 179 and Golden Reef No. 3 and No. 4 in book 127, pages 16 and 17.

They are situated approximately three miles south of Cordes, Yavapai County. Specifically they are in sections 7 and 8, township 10 north and range 2 east.

REFERENCES:

Previous property examination for Shattuck Denn Mining on December 18, 1963 by John Knox.

GEOLOGY:

Examination by the writer concurred exactly with the description by Knox, "Mineralization is localized with an altered shear zone in pre-Cambrian granite. The shear zone contains erratic, lenticular, Quartz stringers. Mining to date has been confined to the oxidized, near-surface portion of the shear where gold values were apparently high enough to justify the operation. Total production has probably been relatively insignificant. Although J. Slak's report on this Property describes the occurrence of base metals in addition to gold, no evidence of these metals could be observed on the dump or along the shear zone outcrop. The shear zone dies out rapidly to the north and though it can easily be followed to the south, the trace metal values appear to be dying out in this direction also."

MINERALIZATION AND MINING:

No samples were collected for assaying by the writer for it was felt that Knox's results are undoubtedly representative.

"The dump, which reportedly averages \$6.00 in gold, assays only about \$1.00; selected dump samples, expected to contain appreciable amounts of gold and silver, contained only traces."

The shaft is apparantly 300 feet deep. It is filled with water and partly caved. It has a 70 degree east direction. It was developed on three levels only, for 150 feet north and south of the shaft. The upper two levels were considerably stoped out.

CONCLUSIONS AND RECOMMENDATIONS:

To evaluate underground workings, it would be necessary to pump an estimated 750,000 gallons of water from the mine.

It would be expected to find only weak mineralization and in a poorly developed structure. Thus, there is little hope for any significant tonnage.

Considering the above in terms of a gold or copper prospect, no interest should be shown in this property.

JOS/ab

cc: Mr. J.C. Pierce

REPORT ON THE HIDDEN TREASURE MIN

Dear Madam:

Pursuant to your request, I submit the following report on the Hidden Treasure Group of mining claims.

LOCATION:

Located about six miles Northwest of Bumble Bee station on the Black Canyon Highway in the Black Canyon Mining District, Yavapai County, State of Arizona.

HOLDINGS:

Holdings consist of ten (10) unpatented claims covering an area of 200 acres. Title held in compliance with the state and the United States laws by location and annual assessment work.

GEOLOGY:

The country rock is Pre-Cambrian schist, which has been intruded by a series of granite porphyry and pegmatite dikes. The geological condition of this property, after a long and careful examination, I find to be gold and silver deposits of deep-seated origin and my conclusion is that it will develop into one of the most important gold districts in the state.

Information gained by the study of this region has thrown new light on the complicated geological structures of this district which gives one a clear picture of the ore bodies at the intersection of the fissure vein and should continue to great depth. This large vein system, highly mineralized is traceable over the entire 200 acres which adds to its production possibilities. The geological history is easily read from the marks on the rocks and time should prove it to be the mother-lode.

The main vein is from 2 to 6 feet in width at the surface, at the depth of 300 ft. it has widened out to the extent of 16 feet; the hanging wall and foot wall are both perfect and persist to great depth.

DEVELOPMENT:

The development consists of shafts and drifts; the main shaft is down 300 ft. on the vein showing commercial values. I am informed that about a 1000 tons of high-grade ore was stoped out and shipped to the smelter some 25 years ago.

WATER:

The Hidden Treasure Mine has a large spring of pure water sufficient to supply a camp and operate a 50 ton mill. The water is piped to the camp and mill-site which is a very valuable asset.

CONCLUSION:

I recommend drifting South on the vein to the intersection of the East and West fissure and contact the dike; this should open up a reservoir of milling ore, of commercial importance that would add another gold producer to Yavapai County. You have a property of great merit which offers an excellent opportunity to develop a large gold mine.

Respectfully submitted,

(signed) A. C. Haigler.

REPORT

on the

Hidden Treasure Mine

Mr. W. A. Bondurant Pres.
Hidden Treasure Mining Co.
Bumble Bee, Arizona.

Dear Sir:

As a result of my recent examination of your highly historic Hidden Treasure Mine, I am enabled to make the following report, which I believe to be correct in every essential respect, and would fully check with the subsequent examiners.

SUMMARY:

Your Hidden Treasure Mine is most excellently situated for mining economically, being on the Prescott-Phoenix, Black Canyon highway, and only about 14 miles by another good road to Bradshaw Mountain where rough mine timber can be had cheaply. Electric power runs over the property and its line is only a few hundred feet from the mine's main workings (such power later). There is an abundance of good water in your Dripping Springs which is connected by a 3 inch pipe line, as well as water from the mine; 10 and 12 miles to Blue Bell siding and Mayer, respectively, at each of which ores and concentrates can be loaded on railroad cars (since this report was made the railroad has been removed). Needless to say that your mine, between surface and 200 feet contains oxidized and very rich, free-milling gold ore. Most of which was worked out during 1901, 1902, 1903 and 1904 by the previous owners, then it was closed down until the spring of 1909, at which time the previous owners put up sufficient funds for the sinking of another 100 feet of the incline shaft on the vein - from 200 foot level 300 foot level. (this writer was connected with the later operation) and as the sinking was progressing the vein was getting bigger and more and more attractive to look at - but the average value was only \$6.00 to \$8.00 in gold per ton, but that was not the only discouragement to the old owners, as the shaft nearing the 300 foot level, spars, and more or less of the complex area commenced to appear within the vein, such as Lead Galena, zinc and copper (Chalcopyrite) and when the 300 foot level was reached the vein was 4ft. wide and showed more and more of the complex ores - in fact too much of it for the old operators, for in these days the least wanted by miners was complex ores. And thus the mine was closed down. (regardless of my urging to continue) and remained closed until you had taken it over some months ago.

Though I was highly pleased at this time in noting your recent exploration on the 300 foot level, in both north and south drifts and especially so in the north drift, you have splendid showing there, and particularly so where you have started to sink the winse, about 60 feet north of the main shaft, as of that point the vein is 10 feet wide and strongly impregnated with high grade lead Galena, lime and copper (chalcopyrite) and in addition the byproduct will be gold and silver and which will help to sell the concentrate when you start to produce.

THE PROPERTY

The property consists of 10 full sized claims all adjoining one another and thus forming a solid group of an area of 200 acres, held under the laws of the United States mineral laws and the requirements of annual ass-

Hidden Treasure
Page Two

assessments has been daily preformed and recorded every year the location. The mine and the mine workings are on the original Hidden Treasure claim, which is practically in the center of the group.

SITUATED

The Hidden Treasure Mine is situated in the Black Canyon Mining District, Yavapai County, Arizona on the old Black Canyon highway, over which to the south is Dumble Bee and about 60 miles to Phoenix; while to the north about 4 miles to Cordes, 12 to Hayer, and 40 miles to Prescott.

GEOLOGY

The country rock in which the Hidden Treasure is situated is the so called Ntalope Hill's Granite, a bolt of which is about 4 miles wide, trending North - South, while near to and along the westerly side line traverses in parallel to the Hidden Treasure vein, the hanging wall of which is granite, and the foot wall a Granodiorite, quartz - porphyry.

VEIN AND CHARACTER OF ORE

The Hidden Treasure vein can be traced over the surface for about 8,200 feet in length, though at many places being covered by wash and debris, trending north - south, 2 feet to 10 feet wide, dipping 65 degrees to the East. with substantial and smooth foot and hanging walls which, underground require but minimum of timbering. The ore within the vein from wall to wall is a brown, strongly iron - stained, brittle quartz, highly porous and closely interwoven with some oxidized iron. This kind of ore, which extends from surface to 200 feet deep, is considered high-grade and free milling in character, while the ore below 200 feet and to near the 300 foot level which (at the present price of gold averages but \$9.00 per ton) would be part free milling and part cyaniding.

ASSAYS OF SAMPLES TAKEN

100' level So. drift \$77.00 in gold, \$1.50 in silver per ton.
200' level So. drift \$76.60 in gold
200' level No. drift \$28.90 in gold

These upper levels if extended both north and south would no doubt disclose several thousands of tons of highgrade gold ore of the kind as shown above. But there is no need of gold at this time nor is there the slightest purpose or interest to mine it. There is but one purpose; To mine ores that contain lead, zinc, and copper, for the war effort. Likewise in addition to highgrade ores in the upper levels, several thousands of tons of lower grade ores can be mined from the 300 foot level up. but that too is out for the duration. One can wait.

ASSAYS

300' level So. drift	\$33.00 gold	\$2.40 silver	0.30% copper
300' " So "	7.00 "	1.30 "	0.65% "
300' " " "	12.00 "	1.40 "	5.40% copper
Lead	3.40%	Zinc	17.95%

Winse 300' level	\$11.10 gold	\$4.62 "	2.55% copper
300' " "	14.00 "	1.96 "	zinc 6.10% lead 4.21%
Lead	10.54%	Zinc	6.00%

These assays as well as my personal observations of conditions on the

Hidden Treasure Mine

300 foot level, fully convince me that from that point on downward the lead, zinc and copper will by far predominate the gold values. And therefore, it is of the highest importance in so far as you and your mine is concerned, that you should resume the sinking of the main shaft from the present 300 foot level - to 500 foot level, as soon as possible, and of establishing such levels and at such points as the conditions may warrant on your downward course.

PRESENT DEVELOPMENT

The present development work consists of 1 - 300 foot deep, 5x7 foot in the clear 650 incline shaft; and about 700 feet of drifts, on the three levels. All the workings are in good condition.

FUTURE DEVELOPMENT

All future development for the development for the duration, should be possible speed and energy below the present 300 foot level such as sinking, drifting, stoping and production.

WATER AND TIMBER

Water is and will be plentiful on the property for likely future operations. One source of it is a large spring in the hills, connected by 3 inch pipe line through which the water comes to the camp with high pressure; while the mine, even now in dry season, makes 8 gallons of water per minute, and it will make more as development progresses. There is no timber on the property, except brush-wood fit for fuel.

TOPOGRAPHY

Practically level, with exception of a few gentle slopes.

ELECTRIC POWER

The electric line traverses the property within a few hundred feet mine proper

ELEVATION

The elevation at the Hidden Treasure Mine is about 3,000 feet above sea level. And then enjoying a most ideal climatic condition which permits mine operations, as well as other activities, the year-round.

TRANSPORTATION

Transportation to and from the mine is excellent through-out the year whether it rains or shines. As the road is situated on the good hard state road.

CONCLUSION & RECOMMENDATIONS

In conclusion I wish but to say that the conditions which I have noted on the 300 ft. level in the Hidden Treasure mine, appear most encouraging. It has all the essential earmarks indicating that the vein, below that level, would open up and develop large and rich bodies of complex ores, and not counting on the inevitable in addition. In other words, the exploration and development of this particular ground offers many odds toward

HIDDEN TREASURE MINE.

success-and but few odds if any toward failure.

Therefore I wish to recommend without hesitation that the present shaft be extended another 200 feet, from 300ft. to 500ft. with extensive drifting to the North and South at both 400 and 500 foot levels.

Respectfully submitted.

By: _____

John Blak
Consulting Mining Engineer
(Registered)

Cordes Arizona
Dec. 5, 1942

COPY

IRON KING MINE
P. O. BOX 68
HUMBOLDT, ARIZONA

SHATTUCK DENN MINING CORPORATION

P. O. BOX 1492
PRESCOTT, ARIZONA

Humboldt

December 18, 1963

D. M. Kentro

Hidden Treasure Mine
Sec. 7, 8 - T10N - R2E

The following briefly summarizes the examination of the Hidden Treasure mine area on Dec. 5, 1963.

The Hidden Treasure mine is located approximately three miles south of Cordes, Yavapai County, Arizona. The property consists of ten unpatented lode claims held by annual assessment work and is owned by Pope and Talbott, Inc., of San Francisco.

Mineralization is localized within an altered shear zone in pre-Cambrian granite. The shear zone contains erratic, lenticular, quartz stringers. Mining to date has been confined to the oxidized, near-surface portion of the shear where gold values were apparently high enough to justify the operation. Total production has probably been relatively insignificant. Although J. Slak's report on this property describes the occurrence of base metals in addition to gold, no evidence of these metals could be observed on the dump or along the shear zone outcrop. The shear zone dies out rapidly to the north, and though it can easily be followed to the south, the trace metal values appear to be dying out in this direction, also. The dump, which reportedly averages \$6.00 in gold, assays only about \$1.00; selected dump samples, expected to contain appreciable amounts of gold and silver, contained only traces.

Six samples were taken from the dump and shear zone. Lead, zinc, and copper were assayed geochemically and the results converted from parts per million to percent.

Sample		Au	Ag	Pb	Zn	Cu
No.	Location					
8401	6' chip across shear zone 100'S of shaft	Tr	Tr	.055	.035	.013
8402	30' " " " " 250' " "	.03	Tr	.015	.013	.004
8403	Dump grab sample	.03	Tr	.140	.033	.009
8404	Quartz from dump	Tr	Tr			
8405	Altered shear zone material from dump	Tr	Tr			
8406	Quartz containing pyrite from dump	Tr	Tr			

DEPARTMENT OF MINERAL RESOURCES

REPORT TO OPA ON ACTIVE MINING PROJECT

Date 5/9/45

Name of Mine Hedden Treasure

Owner or Operator James Otis and Whitace

Address Bumblebee Ariz

Mine Location Between Bumblebee and Crown King.

Filing Information

File System.....

File No.....

This chart to be used for gallons of gasoline required per month.

PRESENT OPERATIONS: (check X)

Production ☒; Development.....; Financing.....; Sale of mine.....;

Experimental (sampling).....; Owner's occasional trip.....;

Other (specify) Reconditioning Mill.

PRODUCTION: Past and Future.

Tons

Approx. tons last 3 months.....

Approx. present rate per 3 months.....

Anticipated rate next 3 months.....

If in distant future check (X) here.....

EQUIPMENT OPERATED:

Type	Quantity or Horse Power	Miles or Hours Per Month	Gallons Required Per Month
Personal Cars			
Light or Service Trucks			
Ore Hauling Trucks	<u>1 truck</u>	<u>2000</u>	<u>250</u>
Compressors	<u>Mill</u>		
Other Mine or Mill Eqpt.	<u>60 HP</u>		<u>750</u>

PRODUCT PRODUCED OR CONTEMPLATED: Name metals or minerals.

Copper lead zinc.

REMARKS:

These people have purchased the Hedden Treasure mill and expect to put it in operation immediately.

ARIZONA DEPARTMENT OF MINERAL RESOURCES

By

Chas H. Dunning

The shaft, which is supposed to be 300 feet deep, is filled with water to within 70 feet of the collar and could not be sampled. Lessors have also apparently gouged out a section of the shaft between 70 and 90 feet of depth, making it questionable as to whether the bottom of the shaft would be accessible even if the water were pumped out.

In general, the mineralization appears to be weak, and the potential for the occurrence of a substantial tonnage of mineable grade material is extremely small. It is recommended that we show no further interest in this property at the present time. However, if the owners should decide to pump the water out of the shaft, it would probably be advisable to examine the mine itself since base metals have been reported from the lowest level.

James A. Knox
James A. Knox

[illegible]

ASSIGNMENT

For and in consideration of the sum of One Thousand Seven Hundred and Fifty Dollars (\$1,750.00), to be paid to the credit of the undersigned at The First National Bank in Prescott, Prescott, Arizona, at the times and in the amounts hereinafter set forth, we, the undersigned, hereby assign, set over, transfer and convey our interest in the attached Bond and Lease, and our interest in the property therein leased, to RALPH DOUGLAS, of Seattle, Washington, and his heirs and assigns:

The sum of \$875. on or before June 9, 1931.
The sum of \$875. on or before Dec. 9, 1931.

Dated at Prescott, Arizona, February 13, 1931.

W.C. Broadgate


Charles D. LaTourrette

Reefing Springs
 Nice Side + Water Right # 225-226
 Box #5
 Page 00

10000
 10000
 10000

North

East
 South



11 claims

West

STATE OF ARIZONA,

County of _____

} ss.

Before me, _____, a Notary Public
in and for the County of _____, State of Arizona, on this day personally appeared

known to me to be the person..... whose name..... subscribed to the foregoing instrument and acknowledged
to me that..... executed the same for the purpose..... and consideration therein expressed.

Given under my hand and seal of office this..... day
of _____, A. D. 19.....

Notary Public.

(My Commission Expires.....)

No.

Bond and Lease
MINING PROPERTY

FROM

TO

Dated,, 191.....

Filed and Recorded at Request of

....., A. D. 191.....

at M.,

Book

Pages

County Recorder.

By
Deputy Recorder.

County Recorder.

WITNESS my hand and official seal the day and year first above written.

of Records of County, Arizona, at pages.....
on this..... day of 19..... and duly recorded in Book No.....
State aforesaid, do hereby certify that the within instrument was filed for record at..... o'clock..... M.,
I, County Recorder in and for the County and

} ss.

STATE OF ARIZONA,

County of

KNOW ALL MEN BY THESE PRESENTS: That
Mrs. J. B. Hayes, a widow,
of the County of Yavapai and State of Arizona,
hereinafter called the part Y of the first part, is held and firmly bound unto
W. C. Broadgate and Charles O. La Tourrette

of the County of Yavapai and State of Arizona,
hereinafter called the part ies of the second part, in the penal sum of
---One Thousand--- DOLLARS,
lawful money of the United States, for the payment of which sum well and truly to be made by the
part Y of the first part to the part ies of the second part, their heirs, executors, adminis-
trators, or assigns, the part Y of the first part hereby binding her self f her heirs,
executors and administrators, firmly by these presents. Witness her hand and seal
this ninth day of February A. D. 19 31.

Whereas, the above bounden part Y of the first part on the day and date hereof, ha s
agreed to sell to the said part ies of the second part or and their assigns the following described property, situated, lying
and being in Black Canyon Mining District, in the County of Yavapai

and State of Arizona, to-wit: The Hidden Treasure Group of eleven (11) lode min-
ing claims, water right and mill site, all recorded in Books of Mines
of Yavapai County Arizona, book numbers, pages and claim names as fol-
lows: Gold Reef, book 95 page 581; Golden Reef #1, book 107 page 175;
Golden Reef #2, book 107 page 176; Golden Reef #3, book 127 page 16;
Golden Reef #4, book 127, page 17; White Tip, book 95 page 582; Curley,
book 95 page 580; Kitty, book 113 page 517; Treasure Mountain, book
117 page 180; Treasure Mountain #2, book 119 page 179, and one uniden-
tified claim adjoining the south end line of the Kitty Claim and lying
between the Golden Reef #2 on the east and the Treasure Mountain #2 on
the west and having the same and parallel side lines.

Dripping Springs water right and mill site, recorded in book 5 of Water
and Mill Sites, Yavapai County, Arizona, pages 225 and 226; excepting
that the party of the first part reserves sufficient water from the
above water right for reasonable domestic purposes.

for the sum of ---Thirty-five Thousand--- DOLLARS,
which said sum is to be paid to the part Y of the first part, or deposited to her credit
in the First National Bank in Prescott, Prescott, Arizona in the manner
following, to-wit: On or before the 9th day of June, A. D. 1931 the
sum of \$ 2,000.00, and a minimum of \$ 2,000.00 each six months there-
after until March 9, 1933, then a payment of one-half of whatever
balance may be due at that time, and a final payment on September 9,
1933, to bring the total payments to a sum of \$ 35,000.00, the sum agreed
upon as the total price of the above mentioned mining property and water

rights. And Whereas, the said part Y of the first part ha s further agreed to make, execute and
acknowledge within thirty days from the date hereof, unto the said part ies of the second
part or assigns, a good and sufficient deed of all the foregoing property, showing a clear and perfect title (ex-
cept as against the United States), free from all incumbrance, which said deed shall be placed, within
thirty days from the date hereof, with The First National Bank of Prescott
in escrow, to be delivered to the said part ies of the second part, or their assigns, on the
payment in full of said purchase money, and

Whereas, the said part Y of the first part ha s further agreed to place the said part ies of
the second part, or their assigns, in full and peaceable possession of said property, to mine,
remove and sell ore therefrom; the said part ies of the second part, or their assigns, to
commence work on said premises before the ninth day of March, A. D. 19 31
and thereafter to work the same continuously in a thorough and workmanlike manner, employing at

least two men underground, working at least thirty shifts to the man each calendar month and to permit the part Y of the first part to have access to all parts of said property at all times and to allow no person not in privity with the parties hereto to take or hold possession of said property or any part thereof under any pretence whatever, and during the continuance of this Bond and Lease to deposit in The First National Bank in Prescott, Prescott, Arizona to the credit of said part Y of the first part ten per centum of the net smelter or mill returns of all ore taken from said property as and when received, said sum so deposited to be a part payment of said purchase money.

AND WHEREAS, it is hereby understood that all buildings, water tanks, and other surface equipment, shall remain, notwithstanding the provisions of this agreement, and also reserves sufficient water from the property of the ~~parties said that first part for its use as a water tank~~ any time should she so desire.

Now, Therefore, the condition of the above obligation is such that if the said part 100 of the second part, or their assigns, shall fail to comply with the terms of the aforesaid agreement, or any of them, time being the essence hereof, and if the said part Y of the first part shall well and faithfully perform the same, then this obligation shall be null and void, otherwise to remain in full force and effect, and in case of such failure all sums paid or deposited as aforesaid shall be retained by the said part Y of the first part as liquidated damages and the part 100 of the second part, or their assigns, shall forthwith surrender possession of said premises.

Signed, Sealed and Delivered in the presence of

Don W. Weatherly

W. A. Klink

Ed Engenbright

Jennie B. Hays (Seal)

W. A. Klink (Seal)

Pharrell D. Hays (Seal)

DEPARTMENT OF MINERAL RESOURCES
STATE OF ARIZONA
OWNERS MINE REPORT

Date

1. Mine **Hidden Treasure**
2. Mining District & County **Black Canyon**
3. Former name **Hidden Treasure**
4. Location
5. Owner **Mrs. Jennie B. Hayes**
6. Address (Owner) **Rt. 12, Box 1134, Phx.
or C/o Hidden Treasure Mine, Cordes,**
7. Operator
8. Address (Operator) **Ariz.**
9. President
10. Gen. Mgr.
11. Mine Supt.
12. Mill Supt.
13. Principal Metals **Gold**
14. Men Employed
15. Production Rate
16. Mill: Type & Cap.
17. Power: Amt. & Type
18. Operations: Present
19. Operations Planned
20. Number Claims, Title, etc. **10 claims, title good.**
21. Description: Topography & Geography
22. Mine Workings: Amt. & Condition **300 ft. shaft and drifts.**

23. Geology & Mineralization

Highly mineralized

24. Ore: Positive & Probable, Ore Dumps, Tailings

Plenty of ore in mine, 40 or 50 thousand dollars of gold in waste dump.

24-A Vein Width, Length, Value, etc.

25. Mine, Mill Equipment & Flow Sheet

26. Road Conditions, Route

Good.

27. Water Supply

Plenty.

28. Brief History

29. Special Problems, Reports Filed

30. Remarks

It can be looked over and I think there is a report on the property.

31. If property for sale: Price, terms and address to negotiate.

If interested I can give all the information you need to make investigation.
It is a good mine.

32. Signed.....

O. H. Craine
Box 1136, Route 12
Phoenix, Arizona

33. Use additional sheets if necessary.

MH-18

DEPARTMENT OF MINERAL RESOURCES
STATE OF ARIZONA
OWNERS MINE REPORT

Mine *Hidden Treasure*
District *Black Canyon*
Former name *Hidden Treasure*
Owner *Mrs Jennie B Hayes* ✓
Operator _____
President _____
Mine Supt. _____
Principal Metals *Silver* ✓
Production Rate _____
Power: Amt. & Type _____
Operations: Present _____

Date

Location

Address *Box 1136 Phoenix*

Address

Gen. Mgr.

Mill Supt.

Men Employed

Mill: Type & Cap.

Operations Planned _____

Number Claims, Title, etc. *10 title good*

Description: Topog. & Geog.

Mine Workings: Amt. & Condition *300 ft shaft and drifts.*

Geology & Mineralization

Highly Mineralized

Ore: Positive & Probable, Ore Dumps, Tailings

Plenty of ore in mine 40 or 50 thousand
Dollars of gold in waste dumps

Mine, Mill Equipment & Flow Sheet

Road Conditions, Route

Good

Water Supply

Plenty

Brief History

Special Problems, Reports Filed

Remarks

It can be looked over and I think there is
a report on the property

If property for sale: Price, terms and address to negotiate.

If interested I can give
all the information you
need to make investigation
it is a good mine.

Resp

Signed

O.H. Craine

R-12 - Box 1136

Use additional sheets if necessary.

Phoenix Arizona